


ANNUAL REPORT
OF THE
ARCHÆOLOGICAL DEPARTMENT

OF

HIS EXALTED HIGHNESS THE NIZAM'S DOMINIONS.



1327 I
1917-18 A.D

CALCUTTA
BAPTIST MISSION PRESS
(1918)

UNIVERSAL
LIBRARY

OU_170874

UNIVERSAL
LIBRARY

ANNUAL REPORT OF THE ARCHÆOLOGICAL DEPARTMENT
OF
HIS EXALTED HIGHNESS THE NIZAM'S DOMINIONS.

ANNUAL REPORT
OF THE
ARCHÆOLOGICAL DEPARTMENT
OF
HIS EXALTED HIGHNESS THE NIZAM'S DOMINIONS.



1327 F.
1917-18 A.D.

CALCUTTA
BAPTIST MISSION PRESS
1919

CONTENTS

OFFICIAL NOTES

	PAGE
Review of Government on the Report	vii
Letter from the Superintendent of Archaeology to the Secretary to Government General (Archaeological) Department	x

REPORT

Personnel	1
Tours .. .	1
Monuments surveyed .. .	1
Conservation ..	11
Excavation ..	12
Epigraphy .. .	13
Numismatics ..	14
Museum ..	14
Hyderabad Archaeological Society ..	14
Publications	14
Library	15
Photographs ..	15
Drawings and Survey Maps	15
Expenditure on Conservation and Survey	15
Expenditure on the Maintenance of Department ..	15
Tour Programme for 1918-19 (1328 F.)	15

APPENDICES

A. Superintendent's Diary	19
B. Statement of Expenditure on the Department	23
C. Conservation and Survey	24
D. List of Books	26
E. Photographs	30
F. Drawings and Survey Maps	32

LIST OF PLATES



PLATE	TITLE
I.	(<i>a</i>) Bībī ka Maqbara, general view (<i>b</i>) Muslim tombs at K̲h̲uldābud (Kauza) general view.
II.	(<i>a</i>) Chāi Minar, Hyderabad City. (<i>b</i>) Chānd Minar Daulatabād, before restoration.
III.	(<i>a</i>) Naldurg Fort, fortifications. (<i>b</i>) Naldurg Fort Pan Mahall (Water Pavilion).
IV.	(<i>a</i>) Plan of Muḥammad Qulī Qutb Shāh's tomb, Golconda. (<i>b</i>) Plan of 'Abdullāh Qutb Shāh's tomb, Golconda
V.	Section of 'Abdullāh Qutb Shāh's tomb, Golconda.
VI.	(<i>a</i>) Plan of the Jāmi' Masjid at Bilohi (Nizāmabād). (<i>b</i>) Plan of the temple at Dichpalli (Nizāmabād)
VII.	Plan of Nāganātha temple at Aundha (Parbhani).

*Proceedings of the Government of His Exalted Highness the Nizam
in the Judicial, Police and General Departments (Archæology).*

No. $\frac{24}{14}$ (Miscellaneous) of $\frac{1328 \text{ F.}}{1919 \text{ A D}}$

DATE, HYDERABAD (DECCAN), 29TH SEPTEMBER, 1919

SUBJECT

Review of the Report on the working of the Archæological Department for the year 1917-18 (1327 F.).

Personnel -Mr. Ghulam Yazdani was in charge of the Department throughout the year

2. *Tours*.—The Superintendent spent a hundred and twenty days in camp visiting a number of monuments in the Dominions, in addition to spending some time at Delhi and Simla to arrange for the taking of estampages of the 'Ala'i Gate inscriptions, which he did successfully.

3. *Inspection of Monuments* -In the Medak District the Superintendent visited the Medak fort, built by the Rajas of Warangal, and a mosque in the Quṭb Shāhī style at Komatur. In the Nizamabad District he inspected a fine temple dedicated to Vishnuite worship at Diehpalli and the programme of repairs suggested by him has been approved of by Government. The Superintendent describes in detail the architectural beauties of the mosque at Biloli (Nānder) still in a good state of preservation. It was built in 1647 by a Mughal Governor named Sarfrāz Khan in a style which is a mixture of the Hindu and Persian architectures of the period. Measures for its conservation, as suggested by the Superintendent are being attended to by the Public Works Department.

The Nāgañatha temple at Aundha, in the Hingoli Taluq of the Parbhani District, the *chef d'oeuvre* of the Chalukyan, or the mediaeval Deccan architecture, was also inspected. The building was never photographed or drawn before, and the several photographs reproduced in the Report for 1326 F (Plates V-VII) and the plan given in the Report (Plate VII) now published for the first time, will convey some idea of the artistic arrangement and the exquisite carvings of this monument. In its structural and decorative features, it is almost a replica of the renowned temple at Halebid, so highly spoken of by Fergusson, and, being an important place of pilgrimage, it is still in a perfect state of repair.

The Superintendent visited a number of places in the Ādilabad District, the most interesting of which are the two caves at Mahur which, judging from their general style, appear to have been excavated about the same time (7th to 9th centuries A.D.) as the late Brahmanical caves at Ellora. One of these caves has silted; but excavation has been started to expose the plinth and other architectural features, while the other, being unfinished, gives an idea of the processes followed by the workers.

4. *Conservation*—His Exalted Highness' Government note with pleasure that, thanks to the efforts of Mr. Nizamu-d-din, Assistant Engineer, Archaeological Works, every cave of the Ajanta series is now in good order and only a few minor improvements remain to be made. In a striking communication addressed to the *Times of India*, the French *savant*, M. Foucher, who visited the caves in 1897 and later in March 1919, has borne testimony to the care and attention bestowed by His Exalted Highness' Government in recent years on the conservation of these caves and in making them easily accessible to the public.

His Exalted Highness' Government have authorised Sir John Marshall to bring out an expert from Italy to examine the paintings and to report on the methods to be adopted to preserve the frescoes from further decay; it is also contemplated to have them reproduced by the three-colour process, for which a comprehensive scheme has been worked out in consultation with Sir Aurel Stein, M. Foucher and Sir John Marshall. Conservation work is also in progress in the historic cities of Bidar and Gulbarga, where a number of monuments were thoroughly repaired and cleaned during the year.

5. *Excavation*.—No extensive operations were carried out by the Department during the year, but Mr. G. E. C. Wakefield, Director General of Industries and Commerce, opened a few cromlechs at Janampet. Their arrangement comprises a single or double ring of stones; a large heavy boulder, weighing several tons, is mounted on three or four stones at the centre, and a monolithic coffin resembling a trough buried below the central boulder. His Exalted Highness' Government hope that the Superintendent will be able to make further investigation himself and enlighten the learned world with his conclusions as regards the nature and origin of these prehistoric remains.

6. *Epigraphy*. The Department was able to obtain a complete set of estampages of inscriptions carved in an old temple and on a boulder near Munirābad, a station on the Guntakal-Gadag line. Mr. H. Krishna Sastri has kindly consented to edit these inscriptions for the *Hyderabad Archaeological Series*, four of which are in Canarese, and the fifth in Tamil. In the domain of Muslim epigraphy the work of publication of the Quṭb Shāhī inscriptions was continued, and two essays, one on the inscriptions in the Golconda Fort and the other on those on the tombs at that place, have already appeared in the *Epigraphia Indo-Moslemica*. The Superintendent intends to take up later the inscriptions of the dynasty in the City and Suburbs of Hyderabad and in other parts of the Dominions.

7. *Numismatics*.—The find of a hoard of eleven hundred and sixty-three coins was reported from the 'Uthmānābad District; but they have not yet been forwarded to the Superintendent, as enquiries by the District Court are still in progress.

8. *Museum*.—Mr. T. Srinivas, Curator of the Hyderabad Museum, was deputed for a period of six months to visit and study the working of museums in other parts of India. He has now returned after gaining much useful experience and His Exalted Highness' Government share the expectation of the Superintendent that by his zeal and energy Mr. Srinivas will make the institution worthy of the premier state of India.

9. *Hyderabad Archaeological Society*.—The Society continued its useful work. Several interesting papers were read and discussed and the members had the unique opportunity of listening to illuminating discourses delivered by Sir Aurel Stein and M. Foucher. A volume of the *Journal* of the Society was published during the year.

10. *Publications*.—In addition to the *Annual Report* for 1916-1917 (1326 F.) the Department published a monograph on the Pālampet and Upparpalli inscriptions as *Hyderabad Archaeological Series* No. 3. The Superintendent edited the *Journal* of the Hyderabad Archaeological Society, 1918, and the *Epigraphia Indo-Moslemica*, 1915-16.

11. *Photographs and Drawings*. All the principal historical buildings in Hyderabad and at Golconda were photographed during the year and four large architectural drawings and a number of small plans and sketches were prepared.

12. *Expenditure*. The expenditure on the maintenance of the Department amounted to Rs. 21,604 as against Rs. 17,181 in 1916-17 (1326 F.), and that on the conservation of the monuments to Rs. 64,721 as against Rs. 33,381.

13. *Conclusion*.—His Exalted Highness' Government are pleased to express their appreciation of Mr. Ghulam Yazdani's enthusiastic work and thank him for submitting a lucid and interesting report.

(By order)

A. HYDARI,

*Secretary to Government, Judicial, Police
and General Departments*

Copy forwarded to : —

1. The Assistant Minister Peshi to His Exalted Highness the Nizam.
2. The Secretary to Government, Political Department.
3. The Secretary to Government, Financial Department.
4. The Secretary to Government, Revenue Department.
5. The Secretary to Government, Public Works Department.
6. The Superintendent of Archaeology.
7. The Superintendent, Government Press, for publication in the *Jarida*.

No 144.

FROM

G YAZDANI, Esq., M.A.,
Superintendent of Archaeology,
His Exalted Highness the Nizam's Dominions.

TO

THE SECRETARY TO GOVERNMENT,
Judicial, Police and General Departments.

Dated Hyderabad (Dn.), the 9th June, 1919

SIR,

I have the honour to submit herewith two copies of the Report on the working of the Archæological Department for the year 1917-18 A.D (1327 Fasli).

A set of the photographs taken during the year under report has already been submitted to Government.

I have the honour to be,
Sir,
Your most obedient servant,
G. YAZDANI,
Superintendent.

Annual Report of the Archæological Department, His Exalted Highness the Nizam's Dominions

for

1917-18 A.D. (1327 F.)

During the year under report there was no change in the personnel of the **Personnel** Department.

The programme of tour given in last year's Report was mainly observed **Tours**. and the Superintendent spent a hundred and twenty days in camp, visiting a number of monuments which had not hitherto been carefully surveyed owing to their being situated at long distances from the Railway line. By the special permission of Government, the Superintendent also visited Delhi and Simla to arrange for the taking of the estampages of the 'Alā'i Gate inscriptions, a task the successful achievement of which, on account of the great height of the gateway, it was considered, would involve a large expenditure on scaffolding. The Superintendent resorted to the simple device of taking two strong ropes, getting the ends of them fastened round the top of the building, and placing a seat in the loop with netting all round to avoid the danger of the person who took the impressions falling out of the seat. This apparatus was raised and lowered along the inscribed surface of the walls from a pulley on the top of the building, and the estampages were secured with perfect convenience and safety.

In last year's Report a reference was made to an inscription set by **Monuments surveyed.** Khafi Khan on the wall of a well at Narsapūr 32 miles north of Hyderabad in the Paigah 'Ilāqa of the late Nawab Khurshīd Jāh. There has been a difference of opinion among scholars as regards the exact significance of the title Khafi Khān. Morley (*Catalogue*, p. 100), led by popular belief which still exists, considered that Khafi was from Khifa 'to conceal,' and that the title had an allusion to the fact that the author's great work, written in spite of Aurangzeb's well-known prohibition, was a concealed account of the monarch's reign. Rieu observes that the author did not enter upon the composition of the work until after Aurangzeb's death, so there could have been no apparent reasons for him to conceal the work. According to Rieu the title is taken from the author's *nisbah* Khawāfi, from Khawāf a district in Khurasan near Naishapur.¹ Elliot also arrived at the

¹ *Catalogue of Persian MSS. in the British Museum*, Vol. I, p. 232b

same conclusion and remarked:—"What is confirmatory of this opinion is that not only does Ghulam 'Alī Shāh style our author Muhammad Hashim, the son of Khwaja Mīr Khwafī, but he himself gives his father's name as Mīr Khwafī."¹ It is not known in what work of the author Elliot saw his father's name. The text of *Muntakhabu-l-lubāb*, published by the Asiatic Society of Bengal, contains the name of one Khwāja Kalān Khwafī, who was the *maternal* uncle (Khalū) of the author, and his *nisba* could not be applied to the author.² The title Khwāfī is not unfamiliar to the students of Indian history, but in no case, has it been abbreviated into Khafī, the form in which it occurs in the *Muntakhabu-l-lubāb* as also in the inscription discovered at Narsapur. In the printed text of *Ma'athiru'l 'Umara'* (Bibl. Ind.) the author is called Khwafī Khan, but it is not known whether Shahnāwaz Khan, in the original manuscript of his work, spelt Khāfī Khan's name in this manner (Khwafī Khān), and if so, for what reasons.³ The spelling, Khafī Khan, adopted in the inscription and used also in the author's history, induces one to agree with Morley that, during Aurangzeb's reign, in spite of his prohibition, there was a historian in 'concealment' who was carefully noticing the events of his reign and who, after the monarch's demise, compiled a history of the period. This view gains support by the author's own statement. He writes:

آنچه خود بعد حد تمیز رسیدن در مدت سی چهل سال برای العین مشاهده نموده بصندوق حافظه سپرده بود بغید فلم در آورد *

"And whatsoever, after arriving at the years of discretion, I had for thirty or forty years seen with my own eyes and laid up in the box of my memory that I have written"

A critical note on the inscription and the life of Khāfī Khan has been contributed to the *Epigraphia Indo-Moslemica*, 1917-18

In November the Superintendent visited the Medak fort. It is similar in construction to the other forts of the Deccan—built on a rocky knoll and fortified with bastions and walls which rise one above the other in several tiers. The fort was apparently built by the Rajas of Warangal, whose special emblem *Gandabherunda* (a double-headed-eagle monster with elephants in its beaks and claws) is carved on a gateway on the back of the Mubārak Mahall. The gates and walls of the fort were in need of slight repairs and the Superintendent has submitted a note to Government embodying adequate measures regarding the conservation of the monuments.

Four miles east of Medak, by the side of a large tank, there is a small village called Komatur. Here, at the northern end of the *band* of the tank, is situated a picturesque mosque of the Quṭb Shāhī style (*Annual Report*, 1916-17, Pl. Ib). It is a small building, consisting of a single hall with three arched openings and flanked with two minarets. The mosque up to the *chhajja* is built of ashlar

¹ *History of India*, Vol. VII, p. 208.

² *Muntakhabu-l-lubāb*, Part II, pp. 19-20.

³ *Ma'athiru'l 'Umara'*, Vol. I, pp. 4, 264 and 451, and Vol. III, p. 680. In this work also in one place (Vol. I, p. 228) the author's name is spelt Khāfī Khān without the *ʿ*.

masonry with fine joints, but above the *chhajja* it is constructed of brick and lime, evidently for the purpose of the cut-plaster decorations which cover the façade and minarets. The beauty of the mosque lies in its perfect symmetry. The building is in a good state of preservation, except the roof and minarets, for the protection of which suitable measures have been proposed to Government.

The fine temple at Dichpalli, ten miles south-east of Nizamabad, was carefully examined and a programme of repairs thereof has been approved by Government. The temple has a picturesque situation, built on an eminence, at the foot of which splash the waters of a large tank. In the middle of the tank there is a pillared hall to which, on festive occasions, the votaries resorted partly for the purpose of worship but chiefly for the sake of enjoyment.

The temple is enclosed by a strong masonry wall which has bastions at the four corners and a gateway facing the North. On entering the enclosure the visitor finds a large court which provides ample space all round the temple. The plan of the building comprises a porch with doors towards North, East and West, a *mandapa* and the cella, or sanctuary. An open *pradakshina* (2' 4" wide) is arranged around the sanctuary, somewhat in an unusual manner, the position of which can best be understood by the accompanying plan (Pl. VIb). In the *pradakshina* circular columns, the form of which is also worthy of notice, are inserted. They are somewhat squat in appearance, having thick cushion-shaped bases, short shafts and square capitals crowned by heavy towers of Dravidian style (*Annual Report*, 1916-17, Pl. IV). The sanctuary has no spire and the temple has other features which show that it was never completed; to wit, the ornamental casing which covers the *mandapa* and the shrine does not extend to the porch, the walls of which are bare and unfinished.

In front of the northern door of the porch two beautiful carved pillars of the form noted above, are fixed. They are detached from the building and at present have no architectural purpose, but if the porch had been completed they would have probably been inserted in the ornamental casing of it. The jambs and the lintels of all the three doors of the porch have fine carvings. The *Gaja-Lakshmi* is represented on the lintels and floral designs and figures of gods and animals appear on the jambs. The porch inwardly measures 14½' × 13½'.

The floor of the *mandapa*, or the main hall, is two steps higher than the porch. The hall is rather plain, having no sculptures or carvings on its walls. It measures 22' 8" × 18' 3".

The cella is entered by a beautiful carved doorway, over the lintel of which the figure of Sri is represented. The interior is square in plan and measures 14' 3" each way. In the centre of the room there is a richly carved seat of black basalt upon which the image of the principal deity of the temple originally rested; but it is vacant now. The seat has an octagonal base and is supported on elegantly carved elephants. The temple is dedicated to Vishnuite worship, and images of the different gods of this cult are arranged in panels along the sides of the seat.

On the exterior of the building a moulded base gives support to the delicately carved niches and pillars which are arranged all round the temple. Above

the pillars and niches there is a deep cornice of the Dravidian type, the face of which is adorned with medallions representing obscene figures. The architecture of the building is of considerable merit, being solid in construction and graceful in finish. The deep cornice, pediments and towers suggest the Dravidian influence.

Another building in the Nizāmabād district, to which the attention of the Superintendent was drawn by the First Taluqdar, is the temple at Jankampet. It is a fairly old structure, but lays no pretension to any architectural or artistic merit. The plan of the building consists of a central *mandapa* (30' × 29' 4"), an ante-chamber (10' 8" × 9'), a shrine (9' 8" × 9') and a pillared hall, styled the *Dharamsala*. There are also some vaulted halls built along the enclosure wall to the south and east of the main temple, but from their style they appear to be later additions.

To the south-west of the temple there is a small tank with a masonry enclosure. Along the sides of the tank colonnades with steps descending to the water level are built for the convenience of bathers.

A Muslim monument of special interest in the Nanded district is the mosque at Biloli (36 miles south-east of Nanded and 10 miles south-west of the Railway station Dharmabad, N.G.S. Railway). It was built by a Mughal governor named Sarfraz Khān in the year 1055 A.H. (1645 A.D.) during the reign of Shahjahan. The architecture of the building is worthy of notice and will be discussed here in some detail. The plan comprises a prayer-hall, a rectangular open court and a masonry cistern at the southern end. The hall has a high basement and is divided into two aisles by a row of massive pillars. At the western end of the hall there is a pentagonal *mihrab*, near the entrance of which a delicately carved pulpit is placed. The roof consists of ten flat domes which are concealed in its thickness. The façade arches, unfortunately, do not look lofty enough for good proportion, but the cornice above is very bold and breaks the depth of masonry over the arches in a pleasing manner. The hall has several windows for ventilation and light. The walls are extremely thick and their peculiarity is that they are double in construction, the space between being coreless.

Two slender and delicately carved minarets stand at the south-east and south-west corners of the hall. They bear a striking resemblance to the minarets of the Kali Masjid at Lakshminishwar in the Dharwar district.¹ The style is a mixture of the Hindu and Persian architecture of the period: to wit, the bases of the minarets and the flexible stone chains which hang from the top are carved in the Hindu style, while the balconies and the form of apex show Persian origin. The chains were evidently cut out of single slabs of stone and their globular pendants, carved as perforated hollow balls with inner balls, when they swing by the action of the air, produce a chime like that of silver bells. On the top of the roof between the minarets there is a beautifully carved stone-screen of lattice work. The minarets and the screen, though extremely pretty in themselves, are not in harmony with the general style of the building, which is quite massive and solid.

¹ *Bijapur Architecture* by H. Cousens, p. 60

Over the prayer niche the following verses are engraved on a marble tablet:—

TEXT.

الله اکبر جل جلاله^۱

- | | | |
|------------------------------|----------------------------|-----|
| که عدل و دادش از ایزد عطا شد | شه صاحب فرمان جود گستر | (1) |
| بدولت صاحب طوغ و لوا شد | ز لطف خاص او خان سرافراز | (2) |
| در اندک مدتی عالی بنیاد شد | فکنده در بلولی طرح مسجد | (3) |
| ز نزهت جلوه گاه اولیا شد | مقام فیض بخش اهل طاعت | (4) |
| فرح بخش دل اهل صفا شد | به نزدش ساخت تالابی و باغی | (5) |
| بسوی بارگاه کبریا شد | ز دل چون خواستم تاریخ مسجد | (6) |
| عبادت گاه حق گویان بنیاد شد | ز هاتف این سرورش عیب بنسید | (7) |

۱۰۵۵ هجری

TRANSLATION.

God is Great and exalted is His Glory¹

- (1) The king, lord of the happy conjunction,² propagator of benevolence ; whom God has blessed with justice and equity.
- (2) By his special favour Sarafrāz Khān³ acquired the distinction of using the standard and the banner
- (3) He laid the foundation of a mosque at Biloli, which soon became a lofty structure.
- (4) A place that conferred beatitude on the pious: and attracted the presence of saints by its purity.
- (5) Near the mosque he built a tank and laid out a garden, refreshing to the soul of pure men
- (6) I asked my intellect for a chronogram of the mosque, it looked for inspiration to the Divine court.
- (7) From the Divine inspirer the invisible spirit (intellect) heard (this) "a place of worship for the truthful is built." 1055 A.H. (1645 A.D.).

To the north of the mosque stands the tomb of Sarafrāz Khān. Its plan consists of a gallery $4\frac{1}{2}$ ft. wide and a square chamber measuring 10' 9" each way. The gallery has three arched openings on each side and a flat stone ceiling. The roof of the grave-chamber is pyramidal. To the south-east of Sarafrāz Khān's tomb there are two more tombs and a masonry platform with some graves on it.

The mosque and the tombs around it are in need of slight repairs and the Superintendent contemplates making the following proposals: (1) The

¹ This phrase is unusual in an inscription of Shāhjahān's reign. The date given in the inscription is 1045, forty years after the death of Akbar. The Dīn Ilāhī ceased at Akbar's death and the occurrence of the phrase here shows only Sarafrāz Khān's interest in the Emperor's religious views.

² The title refers to Shāhjahān, who was the second Mughal monarch after Taimur to hold it.

³ Sarafrāz Khān, during the conquest of the Deccan under Shāhjahān, changed sides according to the fluctuations of the fortunes of the Royalists and the Deccanis. In 1040 A.H. (1630 A.D.) when the Mughal General, Siphadār Khān, conquered the Fort of Situnda (50 miles north-east from Aurangabad), Sarafrāz Khān was the Governor of the Fort under Nizamu-l-Mulk; but later on, in 1060 A.H. (1650 A.D.), he held the Faujdārship of Nadurbar and Sultānpūr under Shāhjahān. See *Muntakhabu-l-lubab*, Pt. I, pp. 437, 455 and 729.

replacing of the earthen enclosures of the mosque by a neat iron railing as soon as prices, which have risen abnormally owing to the War, come to a reasonable level (2) The restoration of the missing stone in the *chhajja*, its design being simple and capable of easy reproduction. The restoration of the *jālī* screen on the roof between the minarets recently done by the Public Works Department, has been a total failure and should not be attempted any more. (3) The careful examination and repair of the damaged portions of the roof, that leaks at one or two places (4) The complete eradication of plants, growing on the walls of the mosque, the roofs of the tombs and the *pucca* platform on which graves are built. (5) The filling of the holes and crevices in the roofs of the tombs by a judicious use of cement and lime-concrete. (6) The thorough cleaning of the land around the mosque and the tombs.

In the 'Adilabad district the Superintendent visited Nirmal, Kadli, Timurni and Mahūr. At Nirmal the only interesting remains are the fortifications of the town, which were built by the French Engineers in the early days of the Āṣaf Jāhī dynasty. The Hindu and Muslim buildings at the place are of little importance.

At Timurni (10 miles west of Nirmal) there is a Muslim tomb called the Dargāh of Shāh Luṭfullāh. Its architecture is interesting, resembling a typical Pathan tomb, with a flat dome and sloping walls (*Annual Report*, 1916-17, Plate IIa). The building stands on a high platform, square in plan and measuring 36 ft. each way. The base of the tomb also is square (24 ft. each way). The inner plan consists of a hall, which is entered by a low doorway of black basalt, built in the pillar-and-lintel style, which in all probability originally belonged to a Hindu temple. The walls were once decorated with enamelled tiles, the remains of which can still be traced.

The temple at Kadli (8 miles north-west of Nirmal) is an old structure dating back from the 12th or 13th century. Its plan consists of an open pillared hall (21' 3" square), an ante-chamber (8' × 5') and a shrine (9' × 8' 9"). In the ante-chamber there are two life-size images of Vishnu and his boar incarnation, Varāha. They are exquisitely carved and exhibit very high workmanship. The door of the shrine is also beautifully carved.

In the *mandapa* there are two niches which contain very pretty images of Vishnu. In the courtyard of this temple there are some loose images lying in a neglected condition. They also are of considerable artistic merit.

The temple is built of chiselled masonry except the spire, which is of brick and lime. The spire is somewhat too large for the building and produces the effect of top-heaviness in the general style.

At Mahūr the Superintendent discovered a pair of caves, cut in the east side of the hill, situated at a distance of three quarters of a mile from the village. The front of the main cave was adorned with six pillars, besides pilasters, but, unfortunately, they have disappeared owing to the fall of the rock forming the façade of the cave. The hall, which measures 77' 6" × 47', has in its middle another row of massive pillars which divide it into two aisles. The pillars have square bases; but after rising to some height, they have been transformed into circular

shafts, and the corners, where the change in the form has taken place, are adorned with human figures, which have decayed owing to the rock being soft and porous. At the western end of the hall is the shrine, measuring 18' \times 18' 6", with a *pradakshina*, or passage for circumambulation, 6' 6" wide. The lintel of the shrine door is adorned with Brahmanical images and pediments of Dravidian order. The interior of the shrine is empty now; but originally it must have had a *linga* with a *salunka*, because the cave, from the presence of the *pradakshina* as also from other features, appears to have been Sivite.

The notable feature of the cave are two gigantic sculptures of *dvārapālas*, each about 14 ft. high, which have been cut with considerable grace and beauty. It is difficult to fix with any certainty the age of the caves; but from their general style they appear to have been excavated about the same time as the late Brahmanical caves of Ellora, that is, somewhere between the 7th and 9th centuries A.D.

Owing to the neglect of centuries, the cave is much silted up; but since the Superintendent's inspection, excavations have been started to expose the original plinth and other architectural features which are now buried under earth and débris.

Outside the cave, at the north-eastern end, there are two unfinished cells, probably intended for the accommodation of Brahmanical deities Ganeśa, Siva and Parvatī.

The other cave, which is unfinished, is as spacious as the first and, if completed, it would have comprised an outer hall with a row of pillars in the front, small rooms at the eastern and western ends, and an inner hall divided into two aisles and flanked with small rooms on the eastern and western sides. The shrine with the *pradakshina* would have been at the southern end of the inner hall.

The cave, though unfinished, gives us an insight into the process which the workmen followed in excavating the caves. The doors are, in the beginning, only irregular openings, the pillars lumps of stone and the halls and rooms irregular and uneven spaces in the heart of the rock. The sculptors first worked out the plan in a rough way and when that was accomplished, they gave proportionate lengths, breadths and altitudes to the various apartments, chiselled the doors, carved the pillars, adorned the façade and finished other architectural and artistic details. The caves are locally called the Pandu Lena.

Among other remains at Māhūr, the most important are the Fort, the Mawāla tank, the Dargāh of Sonā Pir and the Hindu shrines dedicated to Renuka Devi, Dattatreya and Anasuya. The fort was an important outpost of the Deccan kingdoms, because the country in which it is built was always exposed to attacks by the highland chiefs of the Satpuras and by the wild tribes across the Wardha. In 1599 the conquering hosts of Akbar put an end to the Ahmadnagar dynasty, and their kingdom, including Berar, of which Māhūr was a Sarkar, was annexed to the Mughal empire. The fort is very strongly built, perched on a hill 400 ft. high and over-looking the plains below. It has rather an irregular shape, being constructed along the edges of two close-standing spurs, while the valley between

them has been turned into a large tank by the construction of a massive wall. The ascent to the Fort on three sides—East, West and South—is extremely precipitous; the fourth side, which is fairly accessible, was defended by redoubts and stone gateways, the ruins of which can still be traced. Passing beyond these defences, the visitor reaches the main gateway, styled the *Chini Darwāza*, for its façade is decorated with panels of Persian enamel work. The gate is a massive structure, pre-Mughal in appearance and evidently built by the Bahmani kings, who held possession of the Fort for over a century. Inside the gate, on either side of the passage (9 ft. wide), there are spacious rooms which were utilised for the accommodation of the guards. Over the roof of the gate there is an apartment, where probably the Governor of the Fort lived with his family. The apartment opens on a beautiful courtyard with paved walks and a fine masonry cistern in the middle. The northern wall of the apartment is pierced with *jali* screens of artistic design, through which the ladies enjoyed the sight of the cavalcades passing the gateway.

From the *Chini Darwāza* a broad paved road leads the visitor to a group of ruined houses, shown as the various offices and the dwellings of the nobility. The most imposing of these is a rectangular enclosure with high walls, the interior of which is now unfortunately filled with a thick growth of cactus and wild trees and nothing of its plan can be determined.

The *Mawāla* tank is a pleasing expanse of water (532 ft. × 450 ft.), situated at the foot of the hill on which the Fort is built. On three sides it has an enclosure wall (6 ft. high) carrying a fine paved walk (6 ft. broad). For the convenience of the bathers there are broad flights of steps descending to the water level. The fourth side of the tank has been left open to take in monsoon water from the neighbouring hill. The water of the *Mawāla* tank is held in great sanctity, because it is supposed to possess the same potency for blessing the souls of the fair sex as the waters of the holy Ganges for the departed souls of males.

The *Dargāh* of *Sona Pir* is a massive structure of the Pathan style and consists of a large dome, built on a square base. Through lack of care the building has fallen into partial ruin and there are several cracks in the roof to which the Superintendent drew the attention of the Assistant Engineer during his visit to *Māhur*.

The Hindu shrines at *Mahur* have a halo of sanctity and religious tradition about them; but their architecture proves to be very disappointing on close inspection. The bounty of the pilgrims and the religious and utilitarian tastes of the custodians (*pujaris*) are responsible for the destruction of all old structures and the erection, in their place, of arcaded halls of late Muslim type and of square and rectangular rooms with roofs and sheds of corrugated iron sheets.¹

Passing on to the *Parbhani* District, the *Nagānātha* temple at *Aundha* is indeed the *chef-d'œuvre* of the Chalukyan, or the mediaeval *Dekhani* architecture

¹ For a detailed account of the *Mahur* monuments see *Journal of the Hyderabad Archaeological Society*, 1918, pp. 48-50.

in the Dominions. It bears a striking resemblance, in both its structural and decorative features, to the renowned temple at Halebid, the merits of which have been extolled by Fergusson and other authorities. The temple has no inscription to tell us the exact date of its construction; but from its general style it appears to have been built about the same time as its rival at Halebid, *i.e.* the 12th century A D. It was apparently never completed and the spires and some portions of the roofs are later additions. The temple has been fortunate in remaining an important place of pilgrimage, and is, therefore, now in a perfect state of repair.

Aundha is a village in the Hingoli Taluqa of the Parbhani district, and can be approached either from Hingoli, being situated 16 miles south-west of it, or from Chondi—a station on the Purna-Hingoli Railway, Aundha lying only 8 miles from there. A *pucca* road has recently been constructed from Chondi to Aundha; but the only conveyance which can be locally arranged for is a bullock-cart.

The building was never photographed or drawn before, and the several photographs reproduced in last year's Report (Plates V-VII) and the plan given in this Report (Pl. VII) are being published for the first time. The temple is enclosed by a wall 18 to 20 ft high, the lower courses of which are built of dressed masonry and the upper of brick and lime. There are four gates, the largest among them being the Northern, which seems to have been considerably rebuilt during recent times. On entering the temple by this gateway, the visitor notices the eight celestial mothers carved over the lintel of the outer door. Inside the gateway there are cells to the right and the left and on the roof there is an apartment, where the temple's musical band is played at fixed hours.

The plan (Plate VII) explains sufficiently the general arrangement and design of the temple and its various adjuncts. The paved courtyard in which it is built, measures 289 ft. by 190 ft. At the western end of the courtyard there is a raised platform, measuring 152' \times 72', on which there is a domed building named the Samadhi of Namdeo and a *linga* shrine with a square base of chiselled masonry and a *sikhara* of pyramidal form, built in brick and lime. There is another *linga* shrine to the West of the Northern gate and four more near the Eastern gate. In the south-eastern corner of the courtyard there is a beautiful tank with finely chiselled stone margins and a raised seat in the tank itself. Near the western gate there are rows of arched halls called the *Dharmasala*. They have a modern look and seem to have been built recently.

In front of the western portico of the temple there is a raised platform (5 ft. high) with a moulded masonry base. This was originally designed for the Nandi pavilion, which was never built, although a modern *chhatrī*, with four semi-circular arched openings and a pyramidal roof, now occupies the centre of the platform and holds two roughly carved bulls.

The temple itself has a plinth about 5½ ft. high and its entire length from the west portico to the back of the shrine is 126 ft., while the breadth from the northern portico to the southern portico is 118 ft. The inner arrangements consist of a star-shaped *vimana*-*'cella'*—(25' \times 22' 6") in front of which there is a *maha*-

mandapam which is again star-like in form (measuring 40 ft. across), and porticos towards North, South and West. The pillars of the *mahamandapam* are most ingeniously arranged: the central square span has been turned into an octagon by the insertion of two pillars near each corner pillar—the two inserted pillars being in line with one another and forming a right-angled triangle with the corner pillar. This device, which is very pleasing to the eye, has been adopted to support the circular dome of the central compartment of the ceiling. The other compartments are flat and have no carvings, but the heavy entablatures are decorated with images of the Sivite cult. The pillars are extremely graceful, lofty, octagonal in form and most exquisitely carved. The sculptural decoration of the doorways of the shrine and the porticos is also of a very superior kind and, in variety of detail and delicacy, may bear comparison with that of the doorway of any other temple in India. Along the sides of the hall a cornice about 14 inches deep has been built and over that there are niches for the accommodation of the images of the presiding deities of the temple.

There are several bronze images in the shrine, but the chief icon, which has given so much importance to the temple, is a *Jyotirlinga* (*Jyoti*, Light, regarded as the Supreme Spirit), one of the twelve specially celebrated *lingas* scattered throughout India. The *linga* is fixed in an underground chamber in the shrine and is held in great reverence by the votaries of the Sivite cult, who come to worship it from distant parts of India. In the month of Magha a big *jatra* is held annually, in which sixty to seventy thousand pilgrims assemble.

The outer face of the building is divided into bands of friezes carved in relief and running round the structure. Their arrangement from the base is (1) Narasimha heads; (2) elephants, (3) horse riders (*aśvavara*); (4) warriors armed with spikes, clubs, etc., and drummers. Above these four bands the walls are divided into a double course of large panels, the lower of which is occupied by figures of deities in a standing posture and the upper by those in a sitting attitude. In these panels, which extend to several hundred feet, every important god and goddess of the Hindu pantheon finds a place. Some of these representations are interesting from more points than one; to wit, in the lower band of the western façade there is a Mahiṣasuri in front of whom there are four *bairagis* or *san'yasis*, the heads of which are delineated like those of Bhiksus in Buddhist sculptures. In this panel there is another figure, wearing a turban, similar to that of a soldier of the Indian army of to-day. In the southern façade there is a sculpture of Śiva, wearing a curious head-gear resembling an old Roman or Greek helmet such as is represented on Bactrian coins. On the walls of the cella three niches have been built facing North, South, and West. They contain life-size statues of Brahma, Vishnu and Śiva.

The photographs reproduced in last year's Report may convey some idea of the artistic arrangement and the exquisite carvings of this magnificent monument. The remarks made by Fergusson about the design and decoration of the Halebid temple are fully applicable in the case of the Aundha Mandir and may, with the advantage of his superior judgment, be quoted here:—"It must not, however, be considered that it is only for patient industry that this building is"

remarkable. The mode in which the eastern face is broken up by the larger masses, so as to give height and play of light and shade, is a better way of accomplishing what the Gothic architects attempted by their transepts and projections. This, however, is surpassed by the western front, where the variety of outline, and the arrangement and subordination of the various facets in which it is disposed, must be considered as a masterpiece of design in its class. If the frieze of gods were spread along a plain surface, it would lose more than half its effect, while the vertical angles, without interfering with the continuity of the frieze, give height and strength to the whole composition. The disposition of the horizontal lines of the lower friezes is equally effective. Here again the artistic combination of horizontal with vertical lines, and the play of outline and of light and shade, far surpass anything in Gothic art. The effects are just what the mediæval architects were often aiming at, but which they never attained so perfectly as was done at Halebid.'"¹

To the systematic campaign of conservation which has been going on for some years past at Ajanta frequent references have been made in previous reports. Thanks to the energies of Mr. Nizamu-d-din, Assistant Engineer, Archaeological Works, Aurangabad, the work of rescue and cleaning has received an added stimulus during the last year and it is gratifying to be able to record that every cave of this unique series is now in good order.' Some further measures

Conservation.

¹ *History of Indian Architecture* by J. Fergusson and J. Burgess, Vol. I, p. 415

² M. Foucher visited the caves in 1897 and he happened to see them again in March 1910. So his remarks, published in a letter to the *Times of India*, dated March 25, 1910, may be of interest to readers who have no opportunity to see the caves themselves, but are at the same time anxious about their condition and manner of preservation:—

"A little while ago, some criticisms appeared in your esteemed paper, on the way the conservation work is being carried on in the caves of Ajanta. I have no intention whatever to start any controversy in your columns, but as I happen to have visited the Ajanta Caves in September, 1897, and to have been spending the beginning of this month there again, you will perhaps allow me to let you know what are the main alterations I personally observed in them.

"To begin with, I was greatly relieved to hear that I should be spared the long and tiring journey by bullock cart from Pachora to Fardapur, as a new road enables the traveller to reach by *tonga* the immediate vicinity of the caves. These I had for the greater part found open to all kinds of destroying intruders, men or beasts, birds or insects, so that when at work in either *vihara* or *sangharama*, I had no choice left, except between the fierce sun shine outside and the sickening smell of the bats in the interior. The path connecting the different caves was broken in several places, most of the pillars had crumbled down, their remaining stumps giving a jagged and dilapidated appearance to the mouths of the caves, besides the fact that they could no longer support the weight of the overhanging cliff.

"To-day all this has been altered. Neat square pillars—clearly, but unobtrusively modern built of the same stone out of which the caves were hewn—make their existence secure for another good many years. Stone-stairs and a path, with a parapet running along the cliff, lead from cave to cave, some of these having been wholly cleared of the red earth that once silted them, all are kept perfectly clean and, wherever possible, those which contain remnants of paintings have been carefully closed to objectionable guests—bats, nest-building creature, as well as smoke-making *vogis*. Any impartial mind will admit that all these new measures mean a distinct improvement on the previous state of things.

"Of course, it is difficult to please everybody, and criticism is always easy. Nobody will contend that door or window-frames and wire netting, are an embellishment to the caves, but could anyone suggest another way of protecting the paintings? It is a great pity that so many wooden bars should, for instance, cut the beautiful horse shoe windows of the chapels; yet there is no helping it. The only wire-netting able to stand the climate is supplied in small sheets, and requires some kind of frame to be set in those large openings. And so forth. Only one feature I will not attempt to defend. I mean the cement pillars, clumsy imitations of those they replace, and which are still to be seen here and there, a real sore for the eye; but these are anterior by many years to the superintendence of Mr. G. Yazdani, the Nazim of the Archaeological Department in Hyderabad, and a worthy pupil of Sir

have yet to be taken for the improvement of the road and the pathways and the insertion of supports in a few minor excavations newly cleaned; an estimate based on such measures is under preparation in the Public Works Department.

The difficult problem of the preservation and cleaning of the frescoes is also receiving careful attention and H.E.H.'s Government have authorised Sir John Marshall to bring out an expert from Italy to examine the paintings and to report as to what methods can be adopted to save the frescoes from further decay. The Department is equally anxious to keep a faithful and complete record of these matchless paintings for posterity, and to achieve this object a comprehensive scheme has been worked out, in consultation with Sir Aurel Stein, M. Foucher and Sir John Marshall, to have the frescoes reproduced by the three-colour process. Sir John Marshall has also kindly agreed to consult in this matter, during his coming visit to England, the artists of Messrs. Stone & Co., the firm which has so successfully reproduced the banners and frescoes brought from Central Asia by Sir Aurel Stein.

Before leaving the subject of the Ajanta caves it may be observed that for the facility of distinguished visitors and scholars a large rest-house, with accommodation for sixteen or more persons, is being built which, it is hoped, will be ready by the cold season of 1919.

In the historic city of Bidar a start has been made in the programme of conservation drawn up by the Superintendent in 1916. The monuments repaired during the year are :—(1) Madrasah Maḥmūd Gawān (work still in progress), (2) Tomb of Sulṭān Humāyūn, (3) Tomb of Sulṭān Maḥmūd Shāh, and (4) Tomb of 'Alī Barīd. At Gulbargah the handsome building styled the Chōr Gumbad, a short description of which was given in the Report for 1915-16, was thoroughly repaired and cleaned during the year.

Excavations.

No extensive operations were carried out during the year; but Mr. G. E. C. Wakefield, O.B.E., Director of Commerce and Industries, during his tour in the Paloncha Taluqa last summer, opened a few cromlechs at Janampet. The pre-historic graves of this locality were previously examined by Messrs. W. King and Mulheran and a short account of them is published in the *J.A.S.B.*, 1877, Pt. I, pp. 170-85 and *P.A.S.B.*, April and June, 1868. There are several groups of cromlechs scattered in this locality and it is not certain whether Mr. Wakefield examined the same groups which were investigated by Messrs. King and Mulheran.

John Marshall Let me add that the keeping of the caves is entrusted to Mr. Syed Ahmed, a true artist, to whose brush we owe the copies of some of the Ajanta frescoes recently published in London. We may feel sure that ugly blunders, such as the one mentioned above, will not be made again, and that the conservation work will be carried out according to those methods, which have already made their proofs in Sanchi and elsewhere.

"Yet the Hyderabad Government, under the enlightened inspiration of Mr. Hydari, do not feel satisfied with the work already done, entirely at their own expense, here in Ajanta as well as in Ellora. They are now taking steps to secure the best expert advice about the conservation of the paintings themselves, and the possibility of clearing them of the varnish and smoke, which have done so much to darken their colour. They also intend to have these unique remains of ancient Indian painting reproduced in colour by the best photographic process. If I add that I have seen at Pardapur, heaped up on a hill close to the present bungalow, the materials for the erection of a new one, in order to accommodate comfortably the visitors attracted to the place by the fame of the frescoes, we must confess that H.E.H. the Nizam's Government are doing even more than their duty for this great inheritance of old Buddhist India."

The cromlechs noticed by Mr. G. E. C. Wakefield have a striking resemblance to those in Africa and Europe and their arrangement comprises a single or double ring of stones; a large heavy boulder, weighing several tons, is mounted on three or four stones at the centre (in the form of a table), and a monolithic coffin, resembling a trough, buried below the central boulder. The coffin was in some cases found exposed on the surface, which may be due to erosion, as the ground there is not of a uniform level. The special feature noticed by Mr. King, in the cromlechs examined by him, was the presence of cross-shaped tomb-stones. Mr. G. E. C. Wakefield could not trace any of these cross-shaped tomb-stones, although he noticed two wedge-shaped pillars (4 to 5 ft high) with a circular protuberance at the top. The protuberance gave Mr. Wakefield the idea of the head of a human being and he considered the stones represent effigies of man carved by the primitive people. One of the stones, in its upper half, had a pair of concentric rings placed side by side, and Mr. Wakefield surmised that they represented the breasts of a woman and that the stone was the effigy of a female. The cross-shaped tomb-stones noticed by Mr. King and reproduced in the *Journal of the Asiatic Society of Bengal* (1877, Pls. XI-XII) and the wedge-shaped slabs found by Mr. Wakefield show a great contrast in appearance and the latter cannot be identified with a cross.

In the domain of Hindu inscriptions, the salient feature of the year's Epigraphy work is the obtaining of a complete set of estampages of the inscriptions carved in an old temple and on a boulder near Munirabād, a station on the Guntakal Gadag line (Madras and Southern Marhatta Railway). The boulder is lying along the Railway line below the fourth span of the bridge of the Tungabhadra river, about a couple of furlongs from the Munirabad Railway station, towards the Gadag side. The old temple is about half a mile west of Munirabād.

Of these inscriptions, which are five in number, four are Canarese and one Tamil. The most important Canarese record is dated in the 13th year (equivalent to A.D. 1080) of the Western Chalukya king Tribhuvanamalla, *i.e.* Vikramāditya VI. It registers the consecration of the god Someśvara at Pulige,¹ a gift of land for offerings to that god and of money for the recital of the Śivadharmā Purāna. The donor was one Śomeśvara Bhatta, son of Chauvedi Bhaṭṭa and grandson of Narāyana Bhaṭṭa, who was the recipient of the village from the *Chalukya chakrēśvara* Trailōkyamalla. Someśvara I, father of Vikramaditya VI, was known by the *biruda* of Trailōkyamalla (*Bombay Gazetteer*, Vol. I, Pt. 2, p. 438). Mr. H. Krishna Sastri, Rao Sahib, Offg Epigraphist to the Government of India, has kindly agreed to edit this record with critical notes for the *Hyderabad Archaeological Series No. 4*. The other inscriptions are of minor importance.

The work done in Muslim Epigraphy is the continuation of the publication of the Quṭb Shāhī inscriptions, two instalments of which, one relating to the epigraphs in the Golconda Fort and the other on the inscriptions in the Golconda

¹ The village Pulige is said to be situated on the Tungabhadra river and bounded on the east by the Rishyamuṅka mountain, on the south by the Gandhamadana mountain, on the west by the Trikuta mountain and on the north by the Kishkindha mountain.

Tombs, have already appeared in the *Epigraphia Indo-Moslemica*. A third essay is now being compiled on the inscriptions of these kings engraved on buildings in Hyderabad City and Suburbs, which will be published shortly. It is the intention to write a fourth article on the subject, dealing with all such inscriptions as belong to the dynasty but lie scattered in different parts of the Dominions. The object of this series is to present to scholars a systematic and complete study of the inscriptions of the dynasty – fully discussing the origin, development and artistic merits of the various scripts used, the phraseology and literary styles of the texts, critical notes on the dates and identification of the historical persons whose names are mentioned. To the second essay of the series the Superintendent has appended a table giving the chronology of the Qutb Shāhī kings, based on inscriptions in collation with contemporary records, and in the same essay he has also included a brief but accurate account of the political events of the period to enable the reader to study the subject in perspective.

Numismatics. The find of a hoard of 1,163 coins at Muram, in the Usmanabad District, was reported to the Superintendent, who immediately wrote to the First Taluqdar for the transmission of the coins to the Archaeological Department with a view to their being examined and the duplicates being distributed to the various Indian museums in exchange for duplicate coins from their cabinets. The Taluqdar, in spite of repeated reminders, has failed to send the coins to the Superintendent who would now draw the attention of Government to the matter.

The United Provinces Government made a presentation of 59 coins to the Department, and 9 gold coins were similarly received from the Madras Government. These coins have been a valuable addition to the cabinet of the Department, which deeply appreciates the gifts of the above Governments.

Museum. In last year's Report it was noted that Mr. T. Streenivas had been appointed Curator of the Hyderabad Museum. He was subsequently deputed for a period of six months to visit the principal museums in India for the purpose of gaining experience. It is hoped that on Mr. Streenivas's return the Hyderabad Museum will become an accomplished fact and that by his zeal, energy and knowledge, he will make this institution worthy of the premier state of India.

Hyderabad Archaeological Society. The Society has had the most successful year in its life and several very interesting papers were read. Sir Aurel Stein and M. Foucher were kind enough to address the Society during their short stay in Hyderabad and their instructive and illuminating discourses were a real treat to the members of the Society. On the occasion of M. Foucher's visit, the President and Lady Fraser were "At Home," and the opportunity was fully utilized by the members to discuss with the great French *savant* the various points relating to Buddhist art, as represented in the Deccan. A volume of the Journal (No. 4) was issued during the year.

Publications. The following publications were issued by the Department during the year:—

(1) *Annual Report, 1916-17* (1326 F.).

(2) *Inscriptions at Palampet and Upparpalli*, Hyderabad Archaeological Series, No. 3.

In addition, the Superintendent edited the *Journal* of the Hyderabad Archaeological Society, 1918, and the *Epigraphia Indo-Moslemica*, 1915-16, in which several articles are by the Superintendent himself.

119 new volumes were added to the Library of the Superintendent's Office, of which eighty-three were purchased and the rest obtained in exchange for the Department's own publications. A list of the books is given in Appendix D. Library.

The outstanding feature of the year's work is the photographing of all the principal buildings in Hyderabad City and at Golconda, some of which are of supreme importance in the comparative study of Indian architecture. Altogether forty-nine negatives were prepared and a complete set of their prints has been submitted to Government. Photographs.

Four large architectural drawings and a number of small plans and sketches were prepared during the year. Among them the plan and section of 'Abdullah Qutb Shah's tomb show the construction of the dome and various other structural features of that fine monument, a study of which is worthy of the attention of architects interested in the Qutb Shāhī style. The titles, scales, etc., of the large drawings are given in Appendix E. Drawings

The expenditure on the conservation of monuments in the Dominions amounted to U.S. Rs. 64,721 (B.G. Rs. 55,475-2-3), in contrast to U.S. Rs. 33,381-7-8 (B.G. Rs. 28,612-11-2) spent during the previous year (1,326 F.). A detailed statement of the expenditure is given in Appendix C. Expenditure on conservation.

During the year under report a sum of U.S. Rs. 21,604-11-7 (B.G. Rs. 18,518-7-1) was spent on the maintenance of the Department. Details of the expenditure are given in Appendix B. Expenditure on the maintenance of the Department.

In view of the coming visit of Sir Aurel Stein and M. Foucher to Ajanta in connection with the reproduction of the frescos by the three-colour process, a few weeks will be spent in their company to discuss the various proposals on the spot. Further, conservation work of an important nature being in progress in the Bidar and Raichur districts, the Superintendent will have to go to those places as well. If, after these visits, any time is left for touring, it will be devoted to the exploration of the antiquities of the Karimnagar District, about which very little is now known. Tour Programme for 1918-19 (1328 F.).

G. YAZDANI,

Superintendent of Archaeology,

H. E. H. the Nizam's Dominions.

APPENDICES

APPENDIX A

SUPERINTENDENT'S DIARY

(6th October, 1917 to 5th October, 1918—1st *Ādḥ* to 30th *Aban*, 1327 *Fasli*)

Month	Date	Place
1917 A D		
October (1 <i>ḍḥ</i>)	6th 31st (1st-26th)	Duty at headquarters
November (1 <i>ḍḥ</i> & <i>Ḍar</i>)	1st-24th (27th-20th)	Do
"	25th (21st)	Hyderabad to Narsāpur
"	26th (22nd)	Narsāpur to Hyderabad
"	27th-28th (23rd-24th)	Duty at headquarters
"	29th (25th)	Hyderabad to Medak
"	30th (26th)	Halt at Medak
December (<i>Ḍar</i> & <i>Baḥman</i>)	1st (27th)	Do
"	2nd (28th)	Medak to Hyderabad
"	3rd (29th)	Duty at headquarters.
"	4th (1st)	Hyderabad to Dīḥpallī
"	5th (2nd)	Halt at Dīḥpallī
"	6th (3rd)	Dīḥpallī to Nizāmabād
"	7th (4th)	Nizāmabad to Yārpallī
"	8th (5th)	Halt at Yārpallī
"	9th (6th)	Yārpallī to Dīḥpallī
"	10th (7th)	Halt at Dīḥpallī

APPENDIX A —*contd*

Month	Date	Place
December (<i>Bashman</i>)	11th (8th)	Halt at Dichpalli
,	12th (9th)	Dichpalli to Dudgeon
,	13th (10th)	Dudgeon to Numal
,	14th-19th (11th-16th)	Halt at Numal
,	20th (17th)	Numal to Narsapur
,	21st (18th)	Narsapur to Kadli
	22nd (19th)	Kadli to Timurni
,	23rd (20th)	Timurni to Bhamsa
,	24th (21st)	Halt at Bhamsa
	25th (22nd)	Bhamsa to Hyderabad
"	26th-29th (23rd-26th)	Duty at headquarters
"	30th (27th)	Hyderabad to Bilohi
"	31st (28th)	Halt at Bilohi
1918 A D		
January (<i>Bashman</i> & <i>Isjandar</i>)	1st-2nd (29th-30th)	Halt at Bilohi
,	3rd (1st)	Bilohi to Dharmabad
,	4th (2nd)	Dharmabad to Hingoli
	5th (3rd)	Halt at Hingoli
,	6th (4th)	Hingoli to Aundha
,	7th-9th (5th-7th)	Halt at Aundha
"	10th (8th)	Aundha to Boldā

APPENDIX A—*contd*

Month	Date	Place
January (<i>Isfandar</i>)	11th (9th)	Bolda to Shivdara.
	12th (10th)	Shivdarā to Hadgāon
	13th (11th)	Hadgāon to 'Umarkher
,	14th (12th)	'U markher to Hingri
,	15th (13th)	Hingri to Māhur
	16th-24th (14th-22nd)	Halt at Māhur
	25th (23rd)	Māhur to Dharwa
	26th-27th (24th-25th)	Dharwa to Hyderabad
	28th-31st (26th-29th)	Duty at headquarters
February (<i>Isfandar</i> & <i>Farwardin</i>)	1st (30th)	Duty at headquarters
	2nd-28th (1st-27th)	Do
March (<i>Farwardin</i> & <i>Uddih hish</i>)	1st-9th (28th-5th)	Do
	10th (6th)	Hyderabad to Raigri and back
	11th-21st (7th-17th)	Duty at headquarters
,	22nd-23rd (18th-19th)	Hyderabad to Jalgaon
„	24th (20th)	Jalgāon to Ajanta
„	25th-27th (21st-23rd)	Halt at Ajanta
,	28th (24th)	Ajanta to Jalgaon
„	(29th-30th) (25th-26th)	Jalgāon to Hyderabad
	31st (27th)	Duty at headquarters

APPENDIX A—*contd.*

Month	Date	Place
April (<i>Urdibihisht & Khwurdād</i>)	1st-30th (28th-26th)	Duty at headquarters
May <i>Khwurdād & Tir</i>	1st-23rd (27th-18th)	Do.
"	24th (19th)	Hyderabad to Golconda and back.
"	25th-31st (20th-26th)	Duty at headquarters.
June (<i>Tir & Amurdād</i>)	1st-30th (27th-25th)	Do
July (<i>Amurdād</i>)	1st-2nd (26th-27th)	Do
"	3rd (28th)	Hyderabad to Patancherū and back
"	4th-12th (29th-6th)	Duty at headquarters.
"	13th (7th)	Hyderabad to Golconda and back.
"	14th-15th (8th-9th)	Duty at headquarters.
"	16th-17th (10th-11th)	Hyderabad to Jalgāon.
"	18th (12th)	Jalgāon to Ajanta
"	19th-26th (13th-20th)	Halt at Ajanta.
"	27th (21st)	Ajanta to Jalgāon.
"	28th-29th (22nd-23rd)	Jalgāon to Hyderabad.
"	30th-31st (24th-25th)	Duty at headquarters.
August (<i>Shuhriwar & Mīhr</i>)	1st-31st (26th-25th)	Do.
September (<i>Mīhr & Abān</i>)	1st-3rd (26th-28th)	Hyderabad to Delhi (Quṭb)
"	4th-12th (29th-7th)	Halt at Quṭb.
"	13th-14th (8th-9th)	Delhi (Quṭb) to Simla.

APPENDIX A—concl'd.

Month	Date	Place
September (Ābān)	15th-30th (10th-25th)	Halt at Simla.
October (Ābān)	1st-5th (26th-30th)	Do.
In camp	119
At headquarters	246
		<u>365</u>

APPENDIX B

Expenditure on the Archæological Department, Hyderabad, during the year, 6th October, 1917, to 5th October 1918 (1327 F.).

			Rs.	As.	P.	Rs.	As.	P.
Salaries :—								
Superintendent (B.G. Rs. 500—50—600)	8,144	1	5			
Contribution (B.G. Rs. 62-8-0)	875	0	0			
House rent (Rs. 75)	900	0	0			
Establishment	3,210	1	10			
Temporary Establishment	146	3	1			
Grain compensation	55	7	8			
War allowance	320	9	10			
						13,651	7	10
Travelling allowances :—								
Superintendent	2,016	10	5			
Establishment	1,184	10	6			
						3,201	4	11
Contingencies :—								
Fixed Contingencies	999	10	8			
Extra Contin- gencies	Livery for peons	..	60	0	0			
	Purchase of books	..	575	12	2			
	Printing charges	..	2,480	0	0			
	Service postage	..	100	0	0			
	Purchase of furniture	..	191	0	0			
						4,406	6	10
Supply and Services :—								
Purchase of Drawing, Survey and Photo articles	345	11	0			
						345	11	0
GRAND TOTAL							21,604	14 7
							(B.G. 18,518	7 1

APPENDIX C

Statement of expenditure on the Conservation of Ancient Monuments in the Hyderabad State during the year 1917-18 (1327 Fash).

District	Locality	Name of work and description	Amount of sanctioned estimate			Amount spent during the year			REMARKS
			Rs	As.	P.	Rs	As	P.	
Aurangabād	Ajanta	Special repairs to the caves	5	188	0 0	30,420	0	0	Work in progress.
„	„ Aurangabād	Maintenance of Archaeological buildings.	7,750	0	0	6,353	0	0	„
Bidar	Bidar	Repairs to the Kalī Masjid	1	501	0 0	264	0	0	„
„	„	Repairs to the Madrasah of Mahmūd Gāwān	17	980	0 0	8,210	0	0	In progress
„	„	Repairs to the Takht Mahall.	1,291	0	0	966	0	0	„
„	„	Repairs to the tomb of Qāsim Barid	704	0	0	666	0	0	„
„	„ Fort	Repairs to the Rangin Mahall.	800	0	0	753	0	0	„
„	„ Āshūr	Repairs to the tomb of Sultān Muḥammad Shāh.	2,848	0	0	2,397	0	0	„
„	„	Repairs to the tomb of Sultān ‘Ala’u-d-dīn Bahmanī	1,206	0	0	1,145	0	0	„
„	„	Repairs to the tomb of Sultān Humāyūn Shāh	2,502	0	0	2,381	0	0	„
„	„	Repairs to the tomb of Sultān Mahmūd Shāh.	2,486	0	0	2,384	0	0	„
„	„	Repairs to Tirkash Sultān's tomb	768	0	0	168	0	0	„
„	„ Bidar	Repairs to ‘Alī Barid’s tomb.	2,939	0	0	2,592	0	0	„
„	„	Salaries of watchmen.	336	0	0	321	0	0	„
Gulbarga	Gulbarga	Repairs to the Chor Gunbad.	3,080	0	0	2,970	0	0	„
„	„	Maintenance of Archaeological buildings.	322	0	0	308	0	0	„
Carried over			62,298	0	0	

APPENDIX C' *concl'd.*

District	Locality	Name of work and description	Amount of sanctioned estimate			Amount spent during the year			REMARKS
			Rs.	As.	P.	Rs.	As.	P.	
		Brought forward ..				62,298	0	0	
Gulbarga	Gulbarga	Salary of watchman	96	0	0	95	0	0	
Warangal	Pālampet	Salary of watchman	96	0	0	99	0	0	
Rāichūr	Kuknur ..	Repairs to the Nava-linga temple.	5,124	0	0	275	0	0	
Uthmānabād.	Uthmānabād.	Repairs to the caves	9,160	0	0	1,023	0	0	
"	" ..	Maintenance of the Ancient Monuments.	488	0	0	504	0	0	
Nalgonda	Bhongir Fort.	Cutting the jungle ..	375	0	0	96	0	0	
Ādilabād	Mahūr ..	Repairs to the caves			340	0	0	
		Total expenditure 1917-18 (1327 F.)				64,721	0	0	
						(B.G. 55,475	2	3)	

APPENDIX D

List of books in the Library of the Superintendent of Archaeology, Hyderabad, acquired during the year, 6th October, 1917, to 5th October, 1918 (1327 F.).

Serial No	Title	REMARKS
JOURNALS AND PERIODICAL PUBLICATIONS		
505	The <i>Journal</i> of the Royal Asiatic Society of Great Britain and Ireland.	Purchased.
506	The <i>Journal</i> of the Punjab Historical Society, Vol VII, No. 1.	Presented by the Publishers.
507	The <i>Journal</i> of the Bihar and Orissa Research Society, Vol. IV, Parts 1-4, 1918.	Do.
508	The <i>Journal</i> of the Hyderabad Archaeological Society, Vol. III, 1918.	Do.
509-510	The <i>Journal</i> of the Mythic Society, Vol. VIII (Parts 3-4), Vol. IX (Part 1).	Do.
511	The <i>Journal</i> of the Bangya Sahitya, Calcutta, 1918 (3 parts)	Do.
512-13	The <i>Ceylon Antiquary</i> , Vol. III (Part No. 4), Vol IV (Parts 1-2)	Do.
514-15	<i>Bulletin</i> de l'Ecole Française d'Extrême-Orient, Tome XVII Nos 4-6, Tome XVIII, Nos 1-9.	Do.
516	<i>Epigraphia Indo-Moslemica</i> , 1914-15	Purchased.
517-18	<i>Man</i> , published by the Royal Anthropological Institute of Great Britain and Ireland, Vol. XVII, No. 10, Vol. XVIII, No 4.	Presented by the Publishers.
519-20	<i>Indian Architecture</i> , Parts 7-14	Purchased
ARCHAEOLOGICAL SURVEY		
REPORTS—		
521	<i>Annual Report</i> of the Archaeological Survey of India, 1916-17 Part I	Presented by Government of India.
522	Do. Do. 1915-16 Part II .. .	Do.
523	<i>Annual Progress Report</i> of the Superintendent, Hindu and Buddhist Monuments, Northern Circle, 1917.	Do.
524-25	<i>Annual Report</i> of the Superintendent, Muhammadan and British Monuments, Northern Circle, 1917-18.	Do.
526	<i>Report</i> of the Superintendent of Archaeology, Frontier Circle, 1917-18	Do.
527	<i>Annual Report</i> of the Archaeological Superintendent, Eastern Circle, 1916-17	Do.
528	<i>Report</i> of the Archaeological Superintendent, Burma, 1918 ..	Do.
529-30	<i>Annual Progress Report</i> of the Superintendent of Archaeology, Western Circle, 1917-18.	Do.

APPENDIX D—*contd.*

Serial No.	Title	REMARKS
531	<i>Annual Report</i> of the Archaeological Superintendent, Southern Circle, 1917-18.	Presented by Government of India.
532	<i>Report</i> of the Assistant Superintendent of Archaeology for Epigraphy, Southern Circle, 1917-18.	Do.
533	<i>Annual Report</i> of the Archaeological Department, H.E.H. the Nizam's Dominions, 1916-17 (1326 F)	Presented by H.E.H. the Nizam's Government.
534	<i>Annual Report</i> , Mysore Archaeological Department 1918 MONOGRAPHS	Presented by Mysore Durbar
535	<i>Marshall, Sir John</i> , a Guide to Sanchi, 1918 ..	Presented by Government of India.
536	———, a Guide to Taxila, 1918 ..	Do
537	<i>Barnett, L. D.</i> , Inscriptions at Palampet and Uparpalli (Hyderabad Archaeological Series, No. 3). REPORTS (<i>New Imperial Series</i>)—	Presented by H.E.H. the Nizam's Government
538	<i>Cousens II</i> , Bijapur Architecture. Vol XXXVII, 1916 ..	Presented by Government of India.
539	<i>Kavi, G. R.</i> , The Astronomical Observatories of Jai Singh, Vol. XL, 1918	Do.
ART, ARCHITECTURE, ETC.		
540	<i>Brown Percy</i> , Indian Painting, Heritage of India Series ..	Purchased.
541	<i>Fergusson, J.</i> , History of Indian and Eastern Architecture, 1876.	Do.
542	<i>Hobson, R. L.</i> , Porcelain, Oriental, Continental and British, 1906.	Do.
543	<i>Hodgson, W.</i> , How to Identify Old China, 1904 ..	Do.
544	<i>Jouveau-Dubreuil, G.</i> , Pallava Antiquities. Vol. I, 1916	Do.
545	<i>Spiegel, Fr. von</i> , Iranian Art, English translation, ..	Do.
HISTORY, GEOGRAPHY AND TRAVELS.		
BIBLIOTHECA INDICA —		
546	<i>Yazdani, G.</i> , Shāh Jahān Nāmāh, Persian Text, Fasc. III ORIENTAL TRANSLATION FUND NEW SERIES—	Presented by the Editor.
547	<i>Beveridge, A. S.</i> , Humayun Nama of Gulbadan Begam ..	Purchased.
548-49	<i>Rodgers, A., and Beveridge, H.</i> , Tūzuk-i-Jahāngīrī or Memoirs of Jahāngīr 1909	Do.

APPENDIX D—*contd.*

Serial No	Title	REMARKS
RULERS OF INDIA SERIES—		
550	<i>Lane-Poole, S.</i> , Babar, ed. 1909	Purchased.
551	———, Aurangzib, ed. 1908	Do.
552	<i>Malleson, G. B.</i> , Akbar, ed. 1915	Do.
MISCELLANEOUS—		
553-54	<i>Ball, I.</i> , Tavernier's Travels in India, Vols. I-II ..	Do
555	<i>Beal, S.</i> , the Life of Hiuen-Tsiang, Popular edition, Trubner's Oriental Series	Do.
	———, Buddhist Records of the Western World (Si-yu-ki) · Popular edition Trubner's Oriental Series.	Do
556-58	<i>Beveridge, A. S.</i> the Memoirs of Bābur, a New Translation of the Babur-nāma, incorporating Leyden and Fiskine's translation of 1826 A.D., Fascs. I-III	Do
559	<i>Bhandarkar, G. B.</i> , Early History of the Deccan. Written for the Bombay Gazetteer	Do
560	<i>Constable, A.</i> , and <i>Smith, Vincent A.</i> , Travels in the Mughal Empire, A.D. 1656-1668, by François Bernier	Do
561	<i>Gast, E. I.</i> History of Assam, 1906	Do.
562-63	<i>Jarrett, H. S.</i> , The Ain-i-Akbari, by Abul Fazl-i-Allami Vols. II-III	Do
564-65	<i>Kennedy, P.</i> , the History of the Great Moghuls, Vols. I-II ed. 1911	Do
566	<i>Kiepert, H.</i> , Ancient Geography	Do
567	<i>Legge, J.</i> , Travels of Fa-Hien (A.D. 399-414)	Do.
568	<i>Rawlinson, H. G.</i> , Indian Historical Studies, 1913 ..	Do
569	<i>Rushbrook Williams, L. F.</i> , Four lectures on the handling of historical material, Allahabad University Publications, No. 1	Purchased
570-72	<i>Sarkar, Jadunath</i> , History of Aurangzib, Vols. I-III	Do.
GAZETTEERS		
573-98	<i>Imperial Gazetteer</i> of India, Vols. 1-26, New edition, 1909	Purchased.
NUMISMATICS		
599	<i>Codrington, O.</i> , Manual of Musalman Numismatics, 1904 ..	Purchased.
600	<i>Jackson, P. P.</i> , Coin collecting in the Deccan Reprinted from the British Numismatic Journal, Vol. V, 1909 ..	Do.
CHRONOLOGY		
601	<i>Swell, R.</i> , Indian Chronography	Purchased.

APPENDIX D- *concl'd.*

Serial No.	Title	REMARKS
ARCHÆOLOGY.		
602	<i>Bateman, T</i> , Ten years' Diggings in Celtic and Saxon Grave Hills	Purchased
603	<i>Figuer Louis</i> , Primitive Man	Do
604	<i>Jewitt, L.</i> , Grave-mounds and their contents · a Manual of Archaeology.	Do
605	<i>Stevens, E. T.</i> , Flint Chips. a Guide to Pre-historic Archaeology, ed. 1870	Do.
606	<i>Stuart, Villiers</i> , Nile Gleanings, concerning the Ethnology, History and Art of Ancient Egypt, ed. 1879.	Do
607	<i>Westropp, H. M.</i> , Handbook of Archaeology · Egyptian, Greek, Etruscan, Roman, ed. 1867	Do.
608	———, ——— Pre-historic Phases; or, Introductory Essays on Pre-historic Archaeology, ed. 1872.	Do.
• ETHNOGRAPHY, ANTHROPOLOGY AND RELIGION.		
609	<i>Allen, G.</i> , The Evolution of the Idea of God .. .	Purchased
610	<i>Arnold, T. W</i> , The Preaching of Islam, second edition, 1913..	Do
611	<i>Buckland, A W.</i> , Anthropological Studies	Do.
612	<i>Frobenius, Leo</i> , The Childhood of Man Translated by A. H. Keane.	Do.
613	<i>Thurston I</i> , Ethnographic Notes in Southern India ..	Do.
614	<i>Waltz, Theodor</i> Introduction to Anthropology Edited by J F. Collingwood, London, 1863.	Do.
• MISCELLANEOUS		
615-16	<i>Darwin, G.</i> , The Descent of Man Vols I-II	Purchased.
617	———, ——— The Origin of Species	Do
618-19	<i>Haeckel, E.</i> , the Evolution of Man, Vols. I-II	Do.

APPENDIX F.


List of Photographic negatives prepared by the Office of the Superintendent of Archaeology, Hyderabad, during the year 1917-18 (1327 F).

Serial No.	Locality	Description	Size
382	Hyderabad	Siddi 'Anbar ka Bāzār, General view	8½" × 6½"
383		Chār Minar. View from East	"
383a	"	" Another view	6½" × 4½"
384	"	" View from South	"
385	"	" View from North	"
386	"	Chār su ka Hauz and Maḥhlī Kamān	"
387	"	Char Minar	"
387a	"	" Duplicate	"
388	"	Chowk	8½" × 6½"
388a	"	" Another view	6½" × 4½"
389	Golconda	Faṭḥ Darwaza	8½" × 6½"
390	"	Fort, fortifications	"
391	"	" Another view	"
392	"	Zenana palaces	"
393	"	Citadel	6½" × 4½"
394	"	Citadel . Mosque and adjacent buildings	"
395	"	Zenana palaces	"
396	"	Citadel . Door	"
397	"	Golconda tombs and fort : Panoramic view	"
398	"	Tomb of Abdullah Quṭb Shāh	"
399	"	Golconda tombs Panoramic view	"
400	"	" " Another view	"
401	Ellora	Sutār ka Jhonprā (Cave X) . façade	"
402	Ajanta	Cave No XXVI	"
403	Hyderabad	Copy of a Sanad . Upper half	8½" × 6½"
403a	"	" " Lower half	"
404	"	Copy of Sanad No. 1, belonging to Mr. 'Alī Asghar, Home Office.	6½" × 4½"
404a	"	" " Sanad No. 2	"

APPENDIX E—concl'd.

Serial No.	Locality	Description	Size
404 ^b	Hyderabad	Copy of Sanad No. 3	6½" × 4½"
405	Golconda	Qutb Shāhi tombs : General view	"
406	"	Tomb of Abul Hasan	"
407	"	Tomb of Hayat Bakhsh Begam	"
408	"	Tomb of Muḥammad Qutb Shāh	"
409	"	Tomb of Pem Matī	"
410	"	Hakims' (Physicians') tombs	"
411	"	Tomb of Ibrāhīm Qutb Shāh	"
412	"	Ḥammām (Bath) : General view	"
413	"	Fort : View from the tombs	"
414	Rauzā (Auranga- bād.	Tombs : Panoramic view	8½" × 6½"
415	Daulatabād	Chānd Minar : before repairs	"
416	Bidar	Madrasāh Maḥmūd Gāwān : façade	"
417	"	" General view	"
418	Naldurg	Fort : General view	"
419	Medak	Telugu inscription outside the Fort	6½" × 4½"
420	"	"	"
420 ^a	"	"	"
421	Ajanta	Cave XIX . Façade	8½" × 6½"
421 ^a	"	" Interior	6½" × 4½"
422	Hyderabad City	Kālī Kaman . General view	8½" × 6½"
423	Golconda	Fort : Entrances of the citadel.	6½" × 4½"


(a) BIBI KA MAQBARA (AURANGABAD) GENERAL VIEW




(b) TOMBS AT KHULDABAD (AURANGABAD) GENERAL VIEW.



(a) CHAR MINAR HYDERABAD CITY




(b) CHAND MINAR 'DALLATABAD' BEFORE RESTORATION




(a) NALDURG FORT PORTION OF WALL




(b) NALDURG FORT PANI MAHALI (WATER PAVILION)




(a) PLAN OF MUHAMMAD QULI QUTB SHAH'S TOMB AT GOLCONDA.
SCALE 16' TO 1".




(b) PLAN OF ABDULLAH QUTB SHAH'S TOMB AT GOLCONDA.
SCALE 24' TO 1".




TOMB OF ABDULLAH QUTB SHAH.
SECTION ON LINE A B
SCALE 80' = 1".



(a) PLAN OF THE JAMI MASJID AT BULOI (NIZAMABAD).
SCALE 15' TO 1"



(b) PLAN OF THE TEMPLE AT DICHPALLI (NIZAMABAD).
SCALE 15' TO 1"



NAGANATHA TEMPLE AUNDHA (PARBHANI).
SCALE 40' TO 1"

PLATE VII.

